

## **Prior to Installation**

### **TRANSPORT, STORAGE AND ACCLIMATISATION**

Transport and store the cartons in laying position.

Packaged tiles and adhesive should be acclimatized at job site in dry, well-ventilated area for a minimum of 48 hours so that flooring may acclimate.

Remove tiles from packages just before starting laying.

During storage and installation, maintain temperature and relative humidity to a level consistent with the conditions which will prevail when the building is occupied. In most cases, this means maintaining temperature range of 18°C to 28°C (65 F to 82F) and relative humidity range of 35% to 65%. In order to reach this climate, use heating or air conditioning in the appropriate length of time prior to beginning installation.

WICANDERS floorings are natural products and some shade variation is an inherent and attractive characteristic. To achieve the most pleasant blend of shades, shuffle before laying.

### **SITE INSPECTION**

Prior to installation, please inspect the tiles in daylight for any visible faults or damage, and also check if the subfloor and site conditions are in accordance with the specifications described within these instructions.